



WOOD RIVER DRAINAGE AND LEVEE DISTRICT
MADISON COUNTY, ILLINOIS
CLEARING AND STOCKPILE REMOVAL
PROJECT 2025-40
BID DATE: 14 NOVEMBER 2025 AT 2:00PM



CONTRACTOR NAME: _____

NO.	DESCRIPTION	QTY	UNIT	UNIT COST	SCHEDULED VALUE
1	Mobilization/Demobilization	1	LS	N/A	\$
2	Clearing, Grubbing and Disposal	1	LS	N/A	\$
3	Rubble and Stockpiles Disposal	1	LS	N/A	\$
Total:					\$

NOTICE TO BIDDERS

1	820 ILCS 130 - Prevailing Wage Act It is the policy of this District that a wage of no less than the general prevailing hourly rate as paid for work of a similar character in the locality in which the work is performed, shall be paid to all laborers, workers and mechanics employed by or on behalf of any contractor engaged in public works. Certified Payroll shall be submitted in accordance with 820 ILCS 130/5.
2	All trees, stockpiles of previously felled trees, stumps, brush, etc. shall be removed from the site. All stumps and roots shall be removed entirely. All depressions from stumps and root ball removals shall be filled with imported lean clay by placing thin (8-inch loose) lifts and compacting by making 6 passes with tracked equipment.
3	The trees <u>may</u> be chipped or burned onsite. If burning onsite is selected, the Contractor is responsible for obtaining the appropriate permissions and permits from the property owner (Village of Roxana), and the municipality (Village of South Roxana). All of the chips and/or ash must be completely removed from the site. Excavation of burn pits will not be permitted.
4	The rubble stockpiles are believed to be a combination of dirt, broken concrete, broken manholes and lids. Please note that the estimated volume is based on compacted cubic yards. The loose volume may exceed 3,600 CY depending on composition of the stockpiles. If lean clay is found in the stockpiles, it may be utilized to fill root ball depressions.
5	All work onsite must be completed by no later than 30 March 2026.