



PROJECT 2024-29

EAST ALTON NO. 1 PUMP

STATION ROOF REPLACEMENT

JANUARY 2024

Bids Due Date: 01 March 2024

Projected Award Date: 01 March 2024

Project Location: 2750 Berm Highway, East Alton, IL 62024

Project Description: Remove and replace an approximately 2,000 SF roof at the East Alton No. 1 Pump Station. The current roof consists of 2-inches of Poly ISO Roof insulation and a 60-mil EPDM membrane. Replace with 2-inches of new insulation and 60-mil EPDM, TPO, or PVC membrane. By tapering insulation, drainage to scupper in the southeast corner of the structure should be improved.



Site Visits: A site visit is required in order for proposal to be considered. Contact Kevin Williams to schedule. 618-401-7226 or kwilliams@wrld.org.

Permits: Permitting will be handled by the Wood River Drainage and Levee District.

Wage Rates: It is the policy of this District that a wage of no less than the general prevailing hourly rate as paid for work of a similar character in the locality in which the work is performed, shall be paid to all laborers, workers and mechanics employed by or on behalf of any contractor engaged in public works.